

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED SCHEDULE -'B'

Name of Work:-IMPROVEMENTS TO ROADS AND DRAIN AT BALANCE MAIN AND CROSS ROADS AT YELAHANKA OLD TOWN AREAS IN WARD NO.02 OF YELAHANKA SUB-DIVISION

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West)KRIDL, BBMP,	
				Rate	Rate in Words
1	Removing B.S. slab of Drain and stacking.(P No.25 / I N 5.32)	Sqm	423.90	65.72	Rupees sixty five and paise seventy two only
2	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH Chapter 3 (P.142/I.19.1)	Cum	205.17	86.92	Rupees eighty six and paise ninety two only
3	KSRRB M200-24:- dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces no exceeding 0.02 Cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 1000 meters, stacking serviceable and unserviceable materials separately complete as per specifications. MORTH specifications. No. 202, (P.No. 138/ Item No. 18.47)	Cum	276.98	827.86	Rupees eight hundred twenty seven and paise eighty six only
4	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1)	Cum	276.98	166.42	Rupees one hundred sixty six and paise forty two only
5	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1)	Cum	759.12	100.00	Rupees one hundred only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Description	Unit	Approved Qty	Approved Rate Technical Manager (West)KRIDL, BBMP,	
			Rate	Rate in Words
6 Refixing stone slabs of drains and pointing in C.M.(1:3)(P.No.25/I.No.5.33)	Sqm	381.51	80.56	Rupees eighty and paise fifty six only
7 Providing and fixing RCC precast Slabs of 0.10 m thick of CC 1:2:4 with 20 mm and down size graded granite metal , machine mixed , including cost of all material , labour , HOM of Machinery , curing complete	Sqm	42.39	2100.00	Rupees two thousand one hundred only
8 KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications Specification No.KBS 4.1, 4.2 (P.12/I.4.3)	Cum	204.38	5159.02	Rupees five thousand one hundred fifty nine and paise two only
9 Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) M20 for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, for raft foundation, column footing, main and secondary beams with all lead and lifts etc ,complete (exclusive of cost of steel and fabrication charges.) Page No.18 / Item No. 4.48)	Cum	230.81	6231.74	Rupees six thousand two hundred thirty one and paise seventy four only
10 Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift (P.177/I.22.7)	Sqm	1846.50	95.40	Rupees ninety five and paise forty only
11 Providing Groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine generator and HOM of machinery including cost of blade, coolant etc., including cleaning aof groove & providing sand and hot bitumen fillars and filler metal etc.,including cost of conveyance of all materials, labour,lead and lift charges and all the other incidental charges as per drawing and as per specifications, MORTH specification. (P.178/I.22.8)	Mtr	193.00	121.90	Rupees one hundred twenty one and paise ninety only

EXECUTIVE ENGINEER-4
Signature of the Contractor
BENGALURU-560 010

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.